BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2013-14/RD/WORK_INDENT11417

MODIFIED APPROVED SCHEDULE-B

Name of Work:Improvements to Roads and Drains at Maruthinagar Main Road Left Side in Ward No.6 in Dasarahalli Village Limits

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of KODIGEHALLI RAMAKRISHNAPPA SANTOSHKUMAR	
				In Figures	In Words
1	1208.33	Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	89.81	Rupees Eighty Nine and Eighty One Paise Only
2	607.5	Removing B.S. Slab Drain and stacking etc complete as per specifications and directions of engineer in charge of the work	Sqm	49.61	Rupees Forty Nine and Sixty One Paise Only
3	607.5	Refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	69.34	Rupees Sixty Nine and Thirty Four Paise Only
4	99	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, corse aggregates @ 0.85 cum and fine aggregtes @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4247.93	Rupees Four Thousand Two Hundred Forty Seven and Ninety Three Paise Only
5	2178	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	268.37	Rupees Two Hundred Sixty Eight and Thirty Seven Paise Only
6	267.3	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459 cum wuth superplastisier @ 3lts confirming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, wall (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5583.36	Rupees Five Thousand Five Hundred Eighty Three and Thirty Six Paise Only

MODIFIED APPROVED SCHEDULE-B

Tender Notification EE/BTP/BBMP/E-PMT/18/2014-15, Date: 13.01.2014

Name of Work:Improvements to Roads and Drains at Maruthinagar Main Road Left Side in Ward No.6 in Dasarahalli Village Limits

7	187.11	Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery etc complete as per specifications and directions of engineer in charge of the work	Qtl	7376.41	Rupees Seven Thousand Three Hundred Seventy Six and Forty One Paise Only
8	2502.5	Scarifying existing stone metal layer upto 75mm thick along with their bituminous surface, picking up scarified materials and stacking of old serviceable materials with lead of 100m, sequential spreading of the salvaged aggregates with fresh aggregates on prepared base and consolidating as per water bound macadam specifications including cost of all labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	Sqm	72.06	Rupees Seventy Two and Six Paise Only
9	500.5	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	1109.83	Rupees One Thousand One Hundred Nine and Eighty Three Paise Only
10	2502.5	Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	10.42	Rupees Ten and Forty Two Paise Only
11	2502.5	Providing and applying primer coat from 12.2 to 14.6kg per 10 sqm for surfaces of high porosity over prepared surface of granular base with cut back M.C.-70 or any other bitumen mixed with diesel at 13 kg per 10 sqm heated in bitumen boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	Sqm	140.65	Rupees One Hundred Forty and Sixty Five Paise Only
12	62.56	Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specificationsWith 60/70 grade bitumen using 40-60 HMP, etc complete as per specifications and directions of engineer in charge of the work	Cum	9881.55	Rupees Nine Thousand Eight Hundred Eighty One and Fifty Five Paise Only

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2013-14/RD/WORK_INDENT11417

MODIFIED APPROVED SCHEDULE - B

Tender Notification EE/BTP/BBMP/E-PMT/18/2013-14, Date: 13.01.2014

Improvements to Roads and Drains at Maruthinagar Main Road Left Side in Ward No.6 in Dasarahalli Village Limits

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of KODIGEHALLI RAMAKRISHNAPPA SANTOSHKUMAR	
				In Figures	In Words
13	1208	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Cum	71.98	#NAME?

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92